




BATTERY BOX NO DRILL INSTALLATION INSTRUCTIONS



WARNING
DO NOT MISALIGN BOLTS.
BOLTS MUST BE PARALLEL
TO FRAME RAIL FLANGE.



RECOMMENDED BATTERY BOX NO DRILL INSTALLATION:

- 1) MOUNTING BOLTS, NUTS AND WASHER'S ARE NOT SUPPLIED AND ARE TO BE GRADE 5 OR BETTER
- 2) SECURELY FASTEN THE BATTERY BOX AND ANGLE BRACKET (ITEM B) TO THE ANGLE BRACKETS. (ITEM A). USING 1/2" BOLTS, NUTS AND WASHERS.
- 3) TEMPORARILY SUPPORT THE BATTERY BOX AND BRACKETRY ON THE TRACTOR FRAME RAIL. POSITION THE BOTTOM MOUNTING BRACKET, ITEM C ON THE THE FRAME RAIL. MARK THE CENTER OF THE HOLE LOCATION ON THE BATTERY BOX TO FRAME ANGLE BRACKET, ITEM B. THE CENTER OF THE HOLE SHOULD BE IN THE CENTER OF THE ANGLE FLANGE. DRILL THIS HOLE FOR A 5/8" CLEARANCE HOLE.
- 4) MOUNT THE BATTERY BOX TO THE FRAME RAIL USING 5/8" BOLTS, NUTS AND WASHERS. TORQUE THE BOLTS TO 100 FT-LBS. THE BOLTS MUST NOT BE MISALIGNED AS SHOWN IN THE WARNING.

RECOMMENDED MAINTENANCE:

CHECK ALL MOUNTING BOLTS FOR PROPER TORQUE AFTER THE FIRST 1000 MILES OF SERVICE AND PERIODICALLY INSPECT FOR PROPER TORQUE AND SOUNDNESS OF THE ENTIRE BATTERY BOX NO DRILL INSTALLATION EVERY 90 DAYS OR LESS. IF DURING INSPECTION A DISCOVERY OF STRETCHED BOLTS, DAMAGED PARTS, CRACKS IN ANY PART OF THE UNIT, OR A FAILURE OF ANY PART OF THE UNIT IS DISCOVERED THE OPERATOR IS TO IMMEDIATELY REPLACE THE DISCOVERED PROBLEM. DO NOT REUSE MOUNTING KITS THAT HAVE BEEN REMOVED FROM THEIR ORIGINAL APPLICATION.

REVISION	LTR	DATE	DESCRIPTION	BY	SCALE	NONE	 MERRITT ALUMINUM PRODUCTS COMPANY MERRITTPRODUCTS.COM 800-525-0107 1011 14TH ST. FORT LUPTON CO. 80612	
						DWN BY		SPF
						REF #		
						WEIGHT		N/A
					DATE	7/1/16	TITLE BATTERY BOX NO DRILL INSTALLATION INSTRUCTIONS DWG LSRSD0097	